

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-019-19265-00-00
Spot: NENENWSE Sec/Twnshp/Rge: 27-33S-11E
2399 feet from S Section Line, 1637 feet from E Section Line
Lease Name: WADSWORTH Well #: 4
County: CHAUTAUQUA Total Vertical Depth: 1320 feet

Operator License No.: 33157
Op Name: R. D. ENERGY, INC.
Address: 905 N MONTGOMERY
SEDAN, KS 67361

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	6.25	1320		50 SX
SURF	8	30		50 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/20/2018 12:00 AM
Plug Co. License No.: 32884 Plug Co. Name: ELMORE'S, INC.
Proposal Rcvd. from: ROD DICKENS Company: _____ Phone: (620) 725-3065

Proposed Plugging Method: Remove rods and tubing. Run 1" to 1300. Spot 20 sx cement at 1300. Perf casing at 700' and 400'. Run 1" to 700' and spot 20 sx cement. Pull 1' to 400' and cement to surface. Cut off wellhead and weld on top plate.

Plugging Proposal Received By: DUANE SIMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 07/20/2018 2:00 PM KCC Agent: DUANE SIMS

Actual Plugging Report:

Ran 1" to 1250' gelled hole spotted 12 sack plug. Pulled 1" and perforated casing at 750' and 350'. Ran 1" back to 750' and spotted 13 sack plug. Pulled up to 350' and circulated cement to surface. Pulled 1" and topped well off. A total of 141 sacks of cement with 3% gell were used to plug this well. Well was cut off and location restored.

Perfs:

Top	Bot	Thru	Comments
1300	1310		

RECEIVED
KCC DIST # 3
AUG 01 2018
CHANUTE, KS

INVOICED
AUG 02 2018


DS

Remarks:

Plugged through: TBG

District: 03

Signed _____



(TECHNICIAN)