

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-153-20352-00-00
Spot: SESW Sec/Twnshp/Rge: 22-1S-32W
660 feet from S Section Line, 1980 feet from W Section Line
Lease Name: REUBER Well #: 1
County: RAWLINS Total Vertical Depth: 4120 feet

Operator License No.: 5135 String Size Depth (ft) Pulled (ft) Comments
Op Name: FARMER, JOHN O., INC. PROD 4.5 4115 150 SX
Address: 370 W WICHITA AVE PO BOX 352 SURF 8.625 251 180 SX
RUSSELL, KS 67665

Well Type: OIL UIC Docket No: Date/Time to Plug: 07/23/2018 10:00 AM
Plug Co. License No.: 5135 Plug Co. Name: FARMER, JOHN O., INC.
Proposal Rcvd. from: DUANE EICHMAN Company: FARMER, JOHN O., INC. DBA Phone: (785) 483-3145

Proposed Ordered 400 sx 60/40 pozmix 4% gel cement w/750 # hulls.
Plugging 8 5/8" surface casing set at 251' w/180 sx cement.
Method: 4 1/2" production casing set at 4115' w/150 sx cement.
TD 4120', PBT 4021'.
Perforations: 3933' - 3945' and 4063' - 4068'.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/23/2018 1:40 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Perforated production casing at 2738' and 2151'. Ran tubing to 3900' and pumped 90 sx cement w/350 # hulls. Pulled tubing to 2700' and pumped 90 sx cement w/200 # hulls. Pulled tubing to 1350' and pumped 90 sx cement w/150 # hulls. CWC. Pulled tubing to surface. Connected to 4 1/2" production casing and pumped 20 sx cement. Connected to 8 5/8" surface casing and pumped 25 sx cement. Pressured to 300#.

GPS: 39.94594N -100.90005W

Perfs:

Top	Bot	Thru	Comments
4063	4068		
3933	3945		

Received
KANSAS CORPORATION COMMISSION
AUG 02 2018
CONSERVATION DIVISION
WICHITA, KS

INVOICED

AUG 02 2018

Remarks: QUALITY OILWELL CEMENTING TICKET # 874

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN) CM

RECEIVED
KANSAS CORPORATION COMMISSION

JUL 26 2018

AUG 02 2018

CONSERVATION DIVISION
WICHITA, KS