


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Major Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Barton County, Sec. 10 Twp. 20S Rge. (E) 11 (W)

Location as "NE/CNW/SW" or footage from lines C NW NW NW
Lease Owner Clinton Oil Company
Lease Name Ringering Well No. 2-D
Office Address 6810 W. Hiway 54, Wichita, Kansas 67209
Character of Well (completed-as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 23 1968
Application for plugging filed Verbal Approval 1968
Application for plugging approved Verbal Approval 1968
Plugging commenced September 23 1968
Plugging completed September 23 1968
Reason for abandonment of well or producing formation _____



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	RECEIVED FROM	TO	SIZE	PUT IN	PULLED OUT
	STATE CORPORATION COMMISSION		8-5/8"	175'	None
	SEP 30 1968				
	CONSERVATION DIVISION				
	Wichita, Kansas				

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with heavy rotary mud from 3,345' (rotary total depth) to 480 feet. Set bottom plug at 480 feet and cemented with 40 sacks cement by Sun Oilwell Cementing Co. pump truck. Filled hole with heavy rotary mud to 280 feet. Set plug at 280 feet and cemented with 25 sacks cement by Sun pump truck. Filled hole with heavy rotary mud to 40 feet. Set plug and cemented with 10 sacks cement by Sun pump truck.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor H-30, INC.
Address 200 N. Main, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Arlo B. Romer (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Arlo B. Romer
200 N. Main, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of September, 1968

My commission expires April 21, 1971

Martha Hartpence
Notary Public.

KANSAS GEOLOGICAL SOCIETY
 KANSAS WELL LOG BUREAU - KANSAS WELL SAMPLE BUREAU
 KANSAS GEOLOGICAL SOCIETY BUILDING
 508 EAST MURDOCK - WICHITA, KANSAS


15.009.20276.0000

COMPANY **Clinton Oil Company**
 FARM **Ringering** NO. **2-D**

SEC. 10 T. 20S R. 11W
 LOC. C NW NW NW

TOTAL DEPTH **3,345'**
 COMM. **September 16, 1968** COMP. **September 23, 1968**
 SHOT OR TREATED -
 CONTRACTOR **H-30, INC.**
 ISSUED

COUNTY **Barton**



CASING
 20 10'
 15 8-5/8" 175' cemented w/165 sx cement ELEVATION 1768 KB
 12 6
 13 5

FIGURES INDICATE BOTTOM OF FORMATIONS

	40		502	+1266
		<u>SAMPLE TOPS</u>		
Sand & Gravel	40			
Sand	50			
Hard Sand & Sand Rock	65	Anhydrite	502	+1266
Sand & Shale	177	Anhydrite Base	520	+1248
Red Bed & Shale	715	Howard	2548	- 780
Shale & Shells	1000	Topeka	2643	- 875
Salt	1300	Heebner	2911	-1143
Shale & Shells	1377	Toronto	2933	-1165
Shale & Lime	1908	Douglas	2944	-1176
Shale	2370	Brown Lime	3036	-1268
Shale & Lime Streaks	2670	Lansing	3056	-1288
Shale & Lime	2750	Base K.C.	3297	-1529
Lime & Shale	2850	Conglomerate	3307	-1539
Lime	2930	Rotary T.D.	3345	-1577
Lime & Shale	3025			
Lime	3345			
Rotary Total Depth	3345			

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

Arlo B. Romer

 Arlo B. Romer

STATE OF KANSAS }
 COUNTY OF SEDGWICK } SS:

Subscribed and Sworn to before me a Notary Public in and for said county and state this 27th day of September, 1968.

Martha Hartpence

 Martha Hartpence - Notary Public

My Commission Expires:
 April 21, 1971

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 30 1968
 CONSERVATION DIVISION
 Wichita, Kansas