

PLUGGING

FILE SEC 12 T 20 R 116

BOOK PAGE 68 LINE 32

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg. Wichita, Kansas

15.009.14408.0000


Company - E. H. ADAIR OIL CO.
Farm - Werries No. 1

SEC. 10 T. 20 R. 11W
CW $\frac{1}{2}$ E $\frac{1}{2}$ W $\frac{1}{2}$

Total Depth. 3332' PB. 3326'
Comm. 9-17-48 Comp. 11-7-48
Shot or Treated. Shot & Acidized
Contractor.
Issued. 12-25-48

County. Barton

KANSAS



CASING:
8-1/4" 164' 5-3/16" 3299'

Elevation. _____

Production. Dry

Figures Indicate Bottom of Formations.

sand	95
shale & shells	164
shale	198
sand shale red	498
anhydrite	530
shale sdy	590
shale	1320
lime	1465
shale & shells	1750
shale & lime	1825
lime	1850
shale	2442
lime	2480
shale	2665
lime	2965
shale	3031
li o	3332
Total Depth	

Plugged back to 3326 &
shot 1/50 qts., 10-25-48
10-21-48 show oil W/3320,
300 gals. of acid.
11-5-48 oil in hole 600'
no water
11-6-48 Drilling on bailer.
swabbed 300' oil, drove
bailer to 3263'
11-9-48 drilling on bailer
down to 3295'
11-11-48 swabbed 75' oil, but
in lots of wtr, Caved in 15'
closed out bailed hole dry,
put in 30 gals. acid.

Tops: K.B.

Heebner	2904
Brown lime	3028
Lansing	3045
Arbuckle	3301

RECEIVED
DEC 22 1948
STATE OF KANSAS
COMMISSIONER
KANSAS

PLUGGING
FILE SEC. 10 T. 20 R. 11W
BOOK PAGE 68 LINE 32