

KANSAS

*10* STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 17 1966  
10-17-66  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name *Bergman* Jay Panning Oil Company

Complete Address: 425 Union Center, Wichita, Kansas

Lease Name Panning Well No. # 8

Location NE SW SE Sec. 3 Twp. 20 Rge. 11 (E) (W) W

County Barton Total Depth 3302

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Glenn & Smith Pipe Pulling Company

Address: 204 E 6th., Ellinwood, Kansas License No. # 396

Operation Completed: Hour 10:30 AM Day 10 Month 10 Year 1966

The Above well was plugged as follows:

8 5/8" 158' Cwc.

Sanded hole back to 3285' & dumped 5 sax cement with dump bailer. Pulled pipe.

Mudded hole to 160', set rock bridge, & displaced 5 sax cement with dump bailer.

Let set over night, bailed hole dry, & displaced 20 sax cement, Mud to 40', set

rock bridge, & displaced 10 sax cement, cementing to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *Don Leman*  
Well Plugging Supervisor

INVOICED

DATE 10/17/66

INV. NO. 4124-u