

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 418-15

LOCATION NE NE SE

SEC. 3 TWP. 20 RGE. 11-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 8 Lease F. Panning - "C"

Operator Standard Oil & Gas Co Address Box #17, Ellinwood, Kans.

Field _____ County Barton

Total Depth 3303 Feet.

(Describe briefly the manner in which the well was plugged)

*Surface Pipe 17-198 ft. Circulated with cement.
6" casing set at 3284 ft. Cemented with 100 sacks cement.
Plugged back to 3275 ft with chat - Dumped 6 sacks of
cement at 3275 ft - Shot of & pulled the 6" casing -
Mud to 198 ft - Set Rock Bridge & 20 sacks of
cement at 198 ft - Mud to 30 ft - Bridge &
10 sacks of cement at the surface
Miller Casing Pulling Co. Plugging Contractor*

STATE CORPORATION

JAN X 3 1951 1-3-51

CONSERVATION DIVISION
Wichita, Kansas

C. W. Stough
District Conservation Agent

Date 12-31-50

PLUGGING
FILE SEC 3 TWP 20 RGE 11W
BOOK PAGE 48 LINE 15

K 66238

