

DISTRICT CONSERVATION AGENT'S REPORT

B

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 48-16

LOCATION W^{1/2}-W^{1/2}-NE^{1/4}

SEC. 3 TWP. 20 RGE. 11-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 7 Lease C. Rose

Operator Stanford Oil & Gas Co Address Box #7 Ellinwood, Kans.

Field _____ County Barton

Total Depth 3318 Feet.

(Describe briefly the manner in which the well was plugged)

*Surface Pipe 8 3/8-194ft. Circulated with cement
5/8" casing at 3300ft. Cemented with 75 sacks cement.
Plugged back to 3295ft. with shot. Mixed 5 sacks of
cement at 3295ft. Shot off & pulled the 5/8" casing
Mud to 194ft. Set Rock Bridge & 15 sacks of
cement at 194ft. Mud to 30ft. Bridge &
10 sacks of cement at the surface
Miller Pipe Reelting Co. - P. Phillips Contractor*

RECEIVED
STATE CORPORATION COMMISSION
JAN X 8 1951
CONSERVATION DIV.
Wichita, Kan. *C. W. Stough*
District Conservation Agent

Date 1-4-51

PLUGGING
FILE SEC 3 T 20 R 11W
48-16