

15.009.20812.0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 14 1978
CONSERVATION DIVISION
Wichita, Kansas
b-14-78
(of this well)

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 -

Operator's Full Name Bergman Oil Co.

Complete Address 520 Union Center, Wichita, Kansas 67202

Lease Name Schmidt Well No. 4

Location N/2 S/2 SW Sec. 3 Twp. 20 Rge. 11 ~~ØX~~ (W) X

County Barber Total Depth 3304'

Abandoned Oil Well X Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Kelso Casing Pulling

Address Box 176 Chase, Kansas 67524 License No. 683

Operation Completed: Hour 1:15 PM Day 12 Month 6 Year 1978

The above well was plugged as follows:

Sanded back to 3250' and 5 sx cement with dump bailer.

Squeezed thru 8 5/8" surface casing with 4 sx hulls,

20 sx mud gel, 1 sx hulls, plug, and 100 sx cement.

Max pres. 600#. Shut in pres. 200#.

Recovered 1420' of 5 1/2" casing.

3300' of 5 1/2" casing cemented with 225 sx cement.

225' of 8 5/8" surface casing cement circ.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 6-14-78

INV. NO. 7480.0