

KANSAS

¹⁰
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAR 15 1967
3-15-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Colorado Oil Co.

Complete Address: 915 Union Natl. Bldge. Wichita, Kansas

Lease Name ~~Byne~~ Ryno Well No. # 1

Location NE NW NW Sec. 6 Twp. 19 Rge. 1 (W) / (W)

County McPherson Total Depth 3715'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling Co.

Address: Chase, Kansas License No. 436

Operation Completed: Hour 3 PM Day 13 Month 3 Year 67

The Above well was plugged as follows:

8 5/8"-105'-Circulated w/cement. 5 1/2"-3581'-Cemented.

Tubing in hole, top tubing at 2550' to 3715'. Bridge 2550' to 1800'.

10 Sax. cement 1800' to 1730'. Mud 1730' to 150'. Bridge 150' to 140'.

25 Sax. cement 140' to 65'. Mud 65' to 40'. Bridge 40' to 30'.

10 Sax. cement 30' to 0. Pulled 892'-5 1/2"-pipe.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 3/15/67

INV. NO. 4908-W