

15.609.14419.0000

KANSAS.  
STATE CORPORATION COMMISSION

RECEIVED  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

MAY 4 1960

TO:  
Jewel M. Ogden, Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

CONSERVATION DIVISION  
Wichita, Kansas

5-4-60

File No. \_\_\_\_\_ County: Barton

Location: SW SE Sec. 10 Twp. 20 Rge. 11W (E) (W)

Name of Field: \_\_\_\_\_ Total Depth: 3294'

I have this date completed supervision of plugging of:

Lease Name: Panning "E" Well No. # 18

Operator's Full Name: Pan American Petroleum Corp.

Complete Address: Ellinwood, Kansas

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 436, Chase, Kansas License No. # 436

Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_

Other well as hereafter indicated: \_\_\_\_\_

Was any delay in plugging operations caused by Conservation Division Agent? Yes \_\_\_ No

If yes how long? \_\_\_\_\_ Reason: \_\_\_\_\_

Operation Completed: Hour \_\_\_\_\_ Day 28 Month \_\_\_\_\_ Year 1960

The above well was plugged as follows:

Well had been plugged back with 501/2 inch Lane Wells Packer Set  
@ 1300'. No tubing in hole.

Run tubing to 1100', displaced 50 sax cement thru tubing @ 1100'  
with Hallibutyon Cementing Co.'s pump truck. Top of cement was 974'.  
Mud to 200', set rock bridge, & 20 sax cement. Mud to 35', set rock  
bridge, & 10 sax cement, cementing to base of cellar.

Signed: Dave Trumm  
Conservation Division Agent

Reviewed: J. Lewis Brock  
Field Supervisor

Remarks:

INVOICED

DATE 5/6/60

INV. NO. 1298-u