

15.009.14420.0000

Form CP-3
Rev. 6-26-62

44
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

10-29-62

RECEIVED
STATE CORPORATION COMMISSION

OCT 29 1962

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Pan American Petroleum Corp.

Complete Address: Box 1654, Oklahoma City, Oklahoma

Lease Name Panning Well No. 19

Location C NE SE Sec. 10 Twp. 20 Rge. 11 (E) (W)

County Barton Total Depth 3286'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Knight Casing Pulling Co.

Address: Box 304, Chase, Kansas License No. 436

Operation Completed: Hour 3:30PM Day 26 Month 10 Year 1962

The Above well, was plugged as follows:

8 5/8" 211' Cwc.

Sanded hole back to 3265' & dumped 4 sax cement with dump bailer.

Pulled pipe to 400' & circulated hole with mud with mud pump. Pulled

pipe to 200' & displaced 25 sax cement thru pipe. Completed pulling

pipe, set rock ~~xxx~~ bridge, @ 40' & displaced 10 sax cement, cement-

ing to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10/30/62

INV. NO. 5922-W

Signed: Don Truman
Well Plugging Supervisor