

B

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 64-44

LOCATION SW-NE-20W

SEC. 10 TWP. 20 RGE. 11

Dry Hole X Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease putting

Operator Westgate - Greenland Address 4022 Union Natl Bank Bldg - Wichita

Field _____ County Barton

Total Depth 3372 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2" - 160 ft. Circulated with cement. 5 1/2" casing set at 3304 ft. Filled back from bottom to 3300 ft with sand - Pumped 5 sacks of cement at 3300 ft. Shot off & pulled 5 1/2" casing - Filled with mud to 160 ft. Set bridge & 15 sacks of cement at 160 ft. Mud to 80 ft. Plug & 5 sacks of cement at the surface. Bill Morgan - Plugging Contractor

RECEIVED

C. M. Strong
District Conservation Agent

Date 11-15-48

PLUGGING
FILE SEC 10 T 20 R 11W
BOOK PAGE 64 SLINE 44

STATE CORPORATION COMMISSION

11-17-48