

4-020065

10-29

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-009-24,512-0000
70'E. of
SW SW NW /4 SEC. 10, 20 S, 11 W
2970 feet from S section line
4880 feet from E section line

Operator license# 32278

Lease: Lander Well # 2

Operator: Tengasco, Inc.

County: Barton

108.88

Address: P.O. Box 458
Hays, Kansas 67601

Well total depth 3350 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 266 feet

Aband. oil well ☒, Gas well ☐, Input well ☐, SWD ☐, D & A ☐

Plugging contractor: Tengasco, Inc. License# 32278

Address: P.O. Box 458 - Hays, Kansas 67601

Company to plug at: Hour: 10:30 A.M. Day: 29 Month: October Year: 1998

Plugging proposal received from: Terry Piesker

Company: Tengasco, Inc. Phone: 785-625-6374

Were: Ordered 325 sxs 60/40 pozmix - 10% gel - 500# hulls.

Well perforated at 3309' - 3313'.

Well reported to have Dakota leak. Fluid level was 515' and T.D. was 3328'.

11-3-98

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [], Part [X], None []

Completed: Hour: 3:20 P.M., Day: 29, Month: October Year: 1998

Actual plugging report: 8 5/8" set at 266' w/160 sxs. 5 1/2" set at 3348' w/125 sxs.
Ran tubing to 3210' and spotted 110 sxs cement with 150# hulls. Pulled tubing to 1320' and
pumped 110 sxs cement with 150# hulls. Cement circulated. POOH. Tied onto 8 5/8" and
pumped 22 sxs cement. Max. P.S.I. 300#. S.I.P. 250#. Tied onto 5 1/2" and top staged 17
sxs cement. Max. P.S.I. 500#. S.I.P. 300#.

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD BAD

Bottom plug(in place): YES ☒, CALC ☐, NO ☐Plugged through TUBING ☒, CASING ☐.Anhy. plug: YES ☒ NO ☐Dakota plug: YES ☒ NO ☐

Elevation: 1760 GL

I did [X] / did not [] observe the plugging.

(agent)

Form CP-2/3

11-4-98

60261