

12-28 15.009.14421.0000

4-071079

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15- - 12-2-39

E2 E2 SE /4 SEC. 10 , 20 S, 11 W
660 feet from S section line
330 feet from E section line

Operator license# 3613 Lease Panning B well # 20
Operator: Hallwood Petroleum, Inc. County Barton
Address: P.O. Box 378111 Well total depth 3280 feet
Denver, Colorado 80237 Conductor Pipe: 0 inch @ 0 feet
Bruce Hoffman Surface pipe 8 5/8 Inch @ 480 feet

106.60

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Halliburton Services-Klima Well Service License#

Address: Pratt, Kansas - Claflin, Kansas

Company to plug at: Hour: P.M. Day: 28 Month: December Year: 93

Plugging proposal received from: George Hutton - Rick Popp

Company: Hallwood Petroleum, Inc. Phone: 316-792-2756

Were: 8 5/8" - 480' S.P. cwc. w/125 sxs. cement. 5 1/2" casing set @
3273' w/75 sxs. cement. 5 1/2" casing sanded off w/4 sxs. frack sand.
Open hole - casing holes @ 861' - 1079' -490' - 218'. Proposal by Dennis
Hamel - 12 sxs. bentonite gel - 275 sxs. 60/40 pozmix - 10% gel - 1/4#
F.C. Pump in with pump truck. Spot and displace all cement and gel
through tubing. Load both 5 1/2" casing and 5 1/2" x 8 5/8" annulus.
Shut in under pressure.

Plugging Proposal Received by: Dennis L. Hamel
Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 2:00P.M., Day: 28, Month: December, Year: 93

Actual plugging report: Hallwood Petroleum ran 2 7/8 tubing to 1025'.
Couldn't get down - worked on hole two days plus - also tried 1 1/4"
tubing casing bad at 1025'. Don Butcher gave permission to plug at that
depth. 5 1/2" casing was perforated @ 520'. All cement was pumped in with
pump truck. Spotted through 2 7/8" tubing at 1025'- spotted 125 sxs.class
A cement - 150 sxs. pozmix - 10% gel - 12 sxs. gel - 125 sxs pozmix - 6%
gel - 250 sxs. pozmix with salt - 200 sxs. cement - 200 sxs multi cement
R.C. w/8 sxs. hulls. Cement circulated out of 5 1/2" casing and 5 1/2" x
8 5/8" annulus - spotted another 25 sxs. then squeeze casing with an
additional 100 sxs. 60/40 pozmix - 2% gel. Max. Pressure 250 P.S.I.
Remarks: Total cement 1175 sxs. - Cemented by Halliburton Cement.
Condition of casing(in hole):GOOD BAD X Anhy.plug:YES X NO
Bottom plug(in place):YES , CALC , NO Dakota plug:YES X, NO
Plugged through TUBING X, CASING . Elevation: GL

1-5-94 RECEIVED STATE CORPORATION COMMISSION

JAN 05 1994

CONSERVATION DIVISION Wichita, Kansas

I did X / did not observe the plugging.

Mary Schmidt
(agent)

DATE 1-6-94

INV. NO. 39631

12-28