

4-071080

12-21 15.009.14422.0000

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15- - 12-17-39

S2 NW SE /4 SEC. 10, 20 S, 11 W  
1650 feet from S section line  
1980 feet from E section line

Operator license# 3613 Lease Panning B well # 21

Operator: Hallwood Petroleum, Inc. County Barton

Address: P.O. Box 378111 Well total depth 3291 feet  
Denver, Colorado 80237 Conductor Pipe: 0 inch @ 0 feet  
Bruce Hoffman Surface pipe 8 5/8 Inch @ 221 feet

106.96

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Halliburton Services-Klima Well Service License# -

Address: Pratt, Kansas - Claflin, Kansas

Company to plug at: Hour: P.M. Day: 21 Month: December Year: 93

Plugging proposal received from: George Hutton - Rick Popp

Company: Hallwood Petroleum, Inc. Phone: 316-792-2756

Were: 8 5/8" - 221' S.P. cwc. w/125 sxs. cement. 5 1/2" casing set @ 3282' w/75 sxs. cement. Open hole - 3282' - 3291'. Casing good. Proposal by Dennis Hamel 275 sxs. 60/40 pozmix - 10% gel and 12 sxs. bentonite gel. Pump in with pump truck - spot and displace all cement and gel through tubing. Perf. casing @ 1400' - 520' - 260'. Load both 5 1/2" casing and 5 1/2" x 8 5/8" annulus with cement bottom to top. Shut in under pressure.

Plugging Proposal Received by: Dennis L. Hamel  
Plugging operations attended by agent? All [ X ], Part [ ], None [ ]

Completed: Hour: 1:30 P.M., Day: 21, Month: December, Year: 93

Actual plugging report: Hallwood Petroleum ordered 12 sxs. bentonite gel 275 sxs. 60/40 pozmix - 10% gel and 5 sxs. hulls. Pumped in with pump truck spotted and displaced all cement through tubing. 1) Perf. 5 1/2" casing @ 1400' - 520' - 260'. 2) 2 7/8" tubing @ 3200' w/12 sxs. gel. followed with 50 sxs. cement with 2 sxs. hulls added. 3) 2 7/8" tubing @ 1500' w/180 sxs. cement. Cement circulated out of 5 1/2" casing and 5 1/2" x 8 5/8" annulus 4) Squeezed 5 1/2" casing w/45 sxs. cement. Max. pressure 150 P.S.I.

1-5-94

RECEIVED STATE CORPORATION COMMISSION

JAN 05 1994

Remarks: Cemented by Halliburton  
Condition of casing(in hole): GOOD X BAD Anhy. plug: YES X NO CONSERVATION DIVISION  
Bottom plug(in place): YES X, CALC, NO Dakota plug: YES X, NO Wichita, Kansas  
Plugged through TUBING X, CASING. Elevation: GL

I did [ X ] / did not [ ] observe the plugging.

*Marvin Schmidt*  
(agent)

DATE 1-6-94

INV. NO. 39632

12-21