

31
R

4-080192

TO: 6-19 API number: _____
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SE SE SE /4 SEC. 10, 20S, 11 W
200 COLORADO DERBY BUILDING 330 feet from S section line
WICHITA, KANSAS 67202 330 feet from E section line

Operator license# _____ Lease State Riverbed well # 3

Operator: Kansas Corporation Comm County Barton

Address: 2301 East 13th Well total depth 3440 feet
Hays, Kansas 67601 Conductor Pipe: 10 inch @ 62 feet
Mark Casebeer-defunct Surface pipe 7 Inch @ 253 feet

Aband. oil well _____, Gas well _____, Input well _____, SWD XX, D & A _____

Plugging contractor: Kincaid Well Service License# 7252

Address: P. O. Box 726, Ellinwood, Kansas

Company to plug at: Hour: PM Day: 18 Month: June Year: 1996

Plugging proposal received from: Herb Deines

Company: Kansas Corporation Commission phone: 913-628-1200

Were: 4 1/2" inch set at 3281'. Bridge at 838'. Ran tubing to bridge and drilled out 200' of scale. Ran tubing to 2500'. Pumped 50 sx 60/40 poz, 10% gel. Pulled tubing and perforated at 1350', 525'. Ran tubing to 1600'. Pumped 40 sx 60/40 poz, 10% gel. Pulled tubing to 800'. Pumped 120 sx 60/40 poz, 10% gel. Pulled tubing to 400'. Ordered 150 sx 60/40 poz, 10% gel. Pumped 60 sx 60/40 poz, 10% gel, circ cement. Pulled tubing and pumped 20 sx down backside, circ out 4 1/2". Squeezed with 30 sx cem. 450# max, 400 ST.

Plugging Proposal Received by: Bruce Basve
Plugging operations attended by agent? All[XXX], Part[], None[]

Completed: Hour: 7:40 PM, Day: 19, Month: June, Year: 1996

Actual plugging report: Plugged as described above.

0-25822

KANSAS RECEIVED
CORPORATION COMMISSION
JUN 24 1996
CONSERVATION DIVISION
WICHITA, KS
6-24-96

Remarks: Allied cementing on location
Condition of casing(in hole):GOOD _____ BAD X Anhy. plug: YES X NO _____
Bottom plug(in place): YES X, CALC _____, NO _____ Dakota plug: YES X, NO _____
Plugged through TUBING X, CASING _____ Elevation: _____ GL _____

I did[XX] / did not[] observe the plugging. Bruce D. Basve
Bruce D. Basve
(agent)