


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

McPherson County. Sec. 2 Twp. 19S Rge. 1W E/W
Location as "NE/CNW $\frac{1}{4}$ /SW $\frac{1}{4}$ " or footage from lines
NW NW SE

Lease Owner George A. Reed
Lease Name Kaiser Well No. 1
Office Address 645 Fourth Financial Center Wichita, Ks.
Character of Well (Completed as Oil, Gas or Dry Hole) Dry Hole



Locate well correctly on above
Section Plot

Date Well completed 8-30 1977
Application for plugging filed 8-30 1977
Application for plugging approved 8-30 1977
Plugging commenced 8-30 1977
Plugging completed 8-30 1977

Reason for abandonment of well or producing formation
Dry Hole
If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Hugh Scott
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 2891
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

REGISTRATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
STATE CORPORATION COMMISSION WICHITA, KANSAS SEP 07 1977				8 5/8	202	Cemented to surface

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with 55 Vis. Rotary mud from T.D. 2891' up to 220'.
Put in bridge plug and 25 sacks of cement. Filled on up to 40'.
Put in bridge plug and 8 sacks cement. Put 2 sacks in rat hole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Berentz Drilling Company
Box 428 Eureka, Kansas 67045

STATE OF Kansas COUNTY OF Greenwood, ss.
Jack Berentz ~~(owner or operator)~~ or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack Berentz

Box 428 Eureka, Kansas 67045
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of September, 1977

Betty M. Makemson
Betty M. Makemson Notary Public.



LOG OF WELL

Kaiser #1
NW NW SE
Section 2-19-1W
McPherson County, Kansas

OPERATOR: George A. Reed

Elev. KB 1544'

CONTRACTOR: Berentz Drilling Company

Commenced with rotary: 8-24-77

Completed with rotary: 8-30-77

Casing: 8 5/8" --- 202' cemented with 120 sacks

Soil	3'
Shale & Shells	600
Lime w/ Shale Streaks	1280
Shale & Lime	1650
Lime & Shale	1975
Shale & Lime	2286
Lime, Lansing K.C.	2637
Shale & Lime	2800
Sand Shale	2850
Lime Mississippi	2891 R.T.D.

RECEIVED
AUG 31 1977
KANSAS GEOLOGICAL SURVEY