

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-1

File All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation CommissionP. O. Box 17027
Wichita, Kansas 67217

WELL PLUGGING RECORD

Locate well correctly on above
Section Plat

Barton County, Sec. 5 Twp. 20 Rge. 11 (E) W (W)
Location as "NE/CNW/SE/SW" or footage from lines C W/2 SW SW NE
Lease Owner Wayne L. Kirkman Oil Operations
Lease Name Soeken Well No. #2
Office Address 2015 Forest ; Great Bend, Ks. 67530
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19 ____
Application for plugging filed March 19 74
Application for plugging approved March 19 74
Plugging commenced March 5 19 74
Plugging completed May 3 19 74
Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 ____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	203	None
				5 1/2"	3314	1726

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

March 5, 1974

Plugged off bottom. Allied Cementing Co. mixed and pumped down 5 1/2" casing; 1sx of hulls, 5 sx of gel and 100 sx of cement to 2600'.

May 3, 1974

Plugged off top. Allied Cementing Co. mixed and pumped down 8 5/8" surface casing; 3 sx of hulls, 20 sx of gel and 100 sx of cement.

RECEIVED
STATE CORPORATION COMMISSION

7-17-74 JUL 17 1974

CONSERVATION DIVISION
Wichita, Kansas

Name of Plugging Contractor, RUSS CASING PULLING, INC.
Address P. O. Box 1082 ; Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Sedgwick ss.
E. F. Day (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. F. DayBox 18148 Wichita, Ks 67218

(Address)

16th. day of July 19 74

Maxine Dressen

Maxine Dressen

Notary Public.



WELL LOG

O. Soeken #2

C W/2 SW SW NE Section 5-20-11W
Barton County, KansasStarted: May 17, 1952
Completed: May 28, 1952Elevation 1780 KB
Anhydrite 522
Heebner 2926 (-1146)
Lansing 3069 (-1289)
Arbuckle 3313 (-1533)

0-115	Sand and shale
115-203	Sand and blue shale
203-522	Shale, red rock, shells and red bed
522-551	Anhydrite
551-1100	Shale and shells
1100-1320	Salt and shale
1320-1555	Broken lime and shale
1555-1790	Lime and shale
1790-2035	Lime
2035-2345	Shale and lime
2345-2490	Shale and lime
2490-2745	Lime and shale
2745-2835	Lime and shale
2835-2914	Lime
2914-3049	Lime and shale
3049-3135	Lime
3135-3249	Lime
3249-3313	Lime
3313-3316	Arbuckle
3316	TOTAL ROTARY DEPTH

RECEIVED
STATE CORPORATION COMMISSION

MAR 19 1974

CONSERVATION DIVISION
Wichita, Kansas8-5/8" Surface pipe set
at 203' with 145 Sacks
LeHigh cement.New 5 1/4" casing ran at
3314 1/2' with 100 sks. LeHigh Cem.

AFFIDAVIT

STATE OF Kansas, COUNTY OF Barton, SS.

I, Lynn O. Duke of the DUKE & WOOD DRILLING COMPANY, INC.
being first duly sworn on oath, state; That I have knowledge of the facts,
statements and matters herein contained and that the same are true and
correct.

Lynn O. Duke
Vice-President

Subscribed and sworn to before me this 3rd day of June 1952.

Dean T. Looley
Notary Public

My commission expires: April 29, 1953.