

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Building  
Wichita, Kansas

OR

FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plug-  
ging off formations.

Barton County. Sec. 4 Twp. 20 Rge. 11 (E) 11 (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines. SE NE NE

Lease Owner. Isern Brothers

Lease Name. Schmidt Well No. 1

Office Address. Ellinwood, Kansas

Character of Well (completed as Oil, Gas or Dry Hole). Oil

Date well completed. Apr. 26 19. 50

Application for plugging filed. June 12 19. 53

Application for plugging approved. June 19. 53

Plugging commenced. June 22 19. 53

Plugging completed. June 25 19. 53

Reason for abandonment of well or producing formation.

Oil depleted

If a producing well is abandoned, date of last production. March 31 19. 53

Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? yes

Name of Conservation Agent who supervised plugging of this well. C. D. Stough

Producing formation. Arbuckle Depth to top. 3322 Bottom. 3325 Total Depth of Well. 3325 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	207'	none
				5 1/2"	3323'	2581'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Sanded hole from total depth to 3000' and ran 5 sacks of cement at 3000'; Mudded hole from 2950' to 207', set 10' rock bridge and ran 20 sacks of cement. Mudded hole to 35' and set 10' rock bridge and ran 10 sacks of cement on top.

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to. Isern Drilling Company  
Address. Ellinwood, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.

I, W. F. Banks, Production Superintendent (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *W. F. Banks*

Ellinwood, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of July 19. 53

My commission expires. Feb. 10, 1955

PLUGGING  
FILE SEC 4 T 20 R 110  
BOOK PAGE 109 LINE 41

22-237 7-47-10M

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 13 1953 7-13-53  
CONSERVATION DIVISION  
Wichita, Kansas

WELL LOG  
EDW. H. ISEHN, ET AL, OWNERS - Schmidt #1  
SE/4 NE/4 NE/4 Section 4, Township 20, Range 11  
Barton County, Kansas

Elevation: 1783 DF

Pipe Records:

8 5/8" set at 207'  
5 1/2" set at 3323'

Tops

Topoka 2660  
Heebner 2922  
Brown Lime 3049  
Lansing 3067  
Base K.C. 3319  
Arbuckle 3322

Rotary Commenced 4-13-50  
Completed 4-21-50

Cable Tools Commenced 4-22-50  
Completed 4-26-50

Figures indicate bottom of formation  
0 to 60 sand

90 sand & shale  
220 shale & shells  
365 red bed & shale  
420 red bed & sand  
522 red bed  
555 Anhydrite  
1030 Shale & shells  
1215 salt  
1350 shale & shells  
1714 shale & lime  
1735 sand  
2020 shale & lime  
2575 shale & shells  
3070 shale & lime  
3322 lime  
3325 arbuckle  
3325 Total Rotary Depth

3322  
1788  
-----  
1534

3067  
1735  
-----  
1332

CABLE TOOL WORK:

Moved in cable tools, bailed hole, drilled cement and cleaned out hole to total rotary depth.

STATE OF KANSAS )  
                          ) ss  
COUNTY OF BARTON )

I, Edw. H. Isehn, Part Owner, of the above-described well, being first duly sworn on oath, declare: That I have knowledge of the facts, statements and matters herein contained pertaining to the log of the above-described well, as filed, and that the same are true and correct.

Edw. H. Isehn

RECEIVED

Subscribed and Sworn to before me this 23rd day of October, 1950.

JUN 13 1953  
CONSERVATION DIVISION  
Wichita, Kansas

George A. Meyer  
Notary Public

My commission expires February 1951

PLUGGING  
FILE SEC 4 T 20 R 11 W  
BOOK PAGE 107 LINE 41