


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Barton County. Sec. 4 Twp. 20S Rge. 11 ~~XX~~ (W)

Location as "NE/CNW/SW" or footage from lines. Approx SE NW NW  
Lease Owner. Herman Geo. Kaiser  
Lease Name Kummer Well No. 2  
Office Address 909 Palace Building, Tulsa, Oklahoma  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed August 25, 1965  
Application for plugging filed August 25, 1965  
Application for plugging approved August 25, 1965  
Plugging commenced August 25, 1965  
Plugging completed August 25, 1965  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3,334' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	261'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy rotary mud from rotary total depth (3,334 feet) to 260 feet. Set bottom plug at 260 feet and cemented with 1/2 sack hulls and 25 sacks cement. Filled hole with heavy rotary mud to 40 feet. Set top plug at 40 feet and cemented with 1/2 sack hulls and 10 sacks cement, 2 sacks in rat hole.

RECEIVED  
STATE CORPORATION COMMISSION

8-30-65 AUG 30 1965

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor H-30, Inc.  
Address 200 North Main, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, Contractor \_\_\_\_\_  
(employee of owner of well or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Geraldine Hays  
200 North Main, Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of August, 1965

My commission expires December 3, 1968.  
Geraldine Hays Notary Public.

KANSAS GEOLOGICAL SOCIETY  
 KANSAS WELL LOG BUREAU—KANSAS WELL SAMPLE BUREAU  
 KANSAS GEOLOGICAL SOCIETY BUILDING  
 508 EAST MURDOCK - WICHITA, KANSAS


15.009.30125.0000

COMPANY **Herman Geo. Kaiser**  
 FARM **Kummer** NO. **2**

SEC. **4** T. **20S** R. **11W**  
 LOC. **Approx SE NW NW**

TOTAL DEPTH **3,334'**  
 COMM. **8-19-65** COMP. **8-25-65**  
 SHOT OR TREATED  
 CONTRACTOR **H-30, Inc.**  
 ISSUED

COUNTY **Barton**  
 KANSAS



CASING  
 20 10  
 15 5/8" 261.13' cem w/225 sx  
 12 6  
 13 5

ELEVATION **1775 GR**  
**1777 DF**  
**1780 KB**

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

Top Soil	10
Sand	90
Shale & Shells	270
Red Bed	505
Anhydrite	535
Shale & Shells	1375
Shale & Lime	2550
Lime & Shale	3020
Lime	3120
K. C. Lime	3200
Lime	3305
Lime & Shale	3334
Rotary Total Depth	3334

**RECEIVED**  
 STATE CORPORATION COMMISSION

AUG 30 1965

CONSERVATION DIVISION  
 Wichita, Kansas

Sample Tops

Anhydrite Top	505	+1275
Anhydrite Base	535	+1245
Topeka	2651	- 871
Heebner	2915	-1135
Toronto	2932	-1152
Douglas	2947	-1167
Brown Lime	3038	-1258
Lansing	3059	-1279
Base K. C.	3289	-1509
Cherty Conglomerate	3309	-1529
Rotary T. D.	3334	-1554

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

*Garnet B. Douthit*  
 Garnet B. Douthit

STATE OF KANSAS )  
 ) SS:  
 SEDGWICK COUNTY )

Subscribed and sworn to before me, a Notary Public in and for said county and state, this 30th day of August, 1965.

*Geraldine Hays*  
 Geraldine Hays, Notary Public

My Commission Expires:  
 December 3, 1968.