

KANSAS

Form CP-3
Rev. 6-4-68

P

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 16 1978

11-16-78

CONSERVATION DIVISION

Wichita, Kansas

(of this well)

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 009-14397.0000

Operator's Full Name Kaiser-Francis Oil Co.

Complete Address Box 666 Ellinwood, Kansas 67526

Lease Name Duncan "B" Well No. 1

Location C S/2 SW NW Sec. 8 Twp. 20 Rge. 11 ~~XX~~ (W) X

County Barton Total Depth 3322'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Pipe Pullers, Inc.

Address Box 128 Ellinwood, Kansas 67526 License No. 462

Operation Completed: Hour 2:15 PM Day 14 Month 11 Year 1978

The above well was plugged as follows:

Pushed plug to 2780' sanded back to 2760', and 5 sx cement

with dump bailer. Squeezed thru 10 3/4" surface casing

with 2 sx hulls, 10 sx mud gel, 1 sx hulls, and 125 sx cem.

Max. pres. 400#. Shut in pres. 200#.

Recovered 159' of 5 1/2" casing.

3304' of 5 1/2" casing cemented with 150 sx cement.

4 1/2" casing from 2781' to 3304' cemented with 100 sx cem.

197' of 10 3/4" surface casing cement circ.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Duane L. Rankin
Well Plugging Supervisor

DATE 11-16-78
8548-CJ