

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION SE-NW-NE

SEC. 15 TWP. 20 RGE. 11W

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 3 Lease E & M. Gutting

Operator Standard Oil & Gas Co. Address Box 7, Ellinwood, Kans.

Field _____ County Barton

Total Depth 3303 Feet.

Plugging Contractor R & S Pipe pulling Co. Ellinwood Kans.

Plugging Contractor's License No. 1.

Address Ellinwood Kans.

(Describe briefly the manner in which the well was plugged)

Surface pipe 10 3/4 (9) 272' C.W.C. filled back with sand to 3280' and dumped 5 sk of Cem with dump boiler. Shot off and pulled 7" casing which was set 3293' with 50 sk Cem.

Filled hole with mud to 272' set rock bridge and 25 sk of mixed Cem. mud to 30' rock desidge and 10 sk Cem to surface.

RECEIVED
STATE CORPORATION COMMISSION

Warren H. Horner
District Conservation Agent

PLUGGING
BOOK PAGE 134 LINE 13
SEC 15 TWP 20 RGE 11W

Date 12-7-53

12-9-53