


DISTRICT CONSERVATION AGENT'S REPORT



TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 48-14

LOCATION NE-SE-NW

SEC. 11 TWP. 20 RGE. 11-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 3 Lease F. Panning - "A"

Operator Stanford Oil & Gas Co Address Box #17 Ellinwood - Kans.

Field _____ County Barton

Total Depth 3292 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 13' - 186 ft. Circulated with cement.
6" casing set at 3282 ft. Cemented with 100 sacks cement
Plugged back to 3205 ft. with chat - Dumped 6 sacks of
cement at 3275 ft. Picked off & pulled the 6" casing -
Filled hole with sand to 186 ft. Rock Bridge &
25 sacks of cement at 186 ft. Mud to 30 ft. Bridge
& 10 sacks of cement at the surface
A.S. Pipe Pulling Co. - Plugging Contractors

RECEIVED
STATE CORPORATION COMMISSION

JAN X 5 1951

WICHITA, KANSAS
District Conservation Agent

Date 1-3-51

PLUGGING
FILE SEC 11 TWP 20 RGE 11W
BOOK PAGE 48 LINE 14