

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 147-13LOCATION 2 1/2 - 3 1/2 - NE 1/4SEC. 11 TWP. 20 RGE. 11EDry Hole Abandoned Oil Well X Abandoned Gas Well

I have today completed supervision of plugging of:

Well No. 11 Lease P. KowalskiOperator Standard Oil Co. Address Box #7 - Ellinwood KanField County BartonTotal Depth 3295 Feet.

(Describe briefly the manner in which the well was plugged)

Surf. Pipe 10 3/4 - 212 ft. Circulated with cement.
7" casing at 3284 ft. - Plugged back to 3270 ft
with shot - Dumped 6 sacks of cement at 3270 ft -
Shot off & pulled the 7" casing - Filled with mud
to 212 ft - Rock Bridge & 20 sacks of cement at 212 ft -
Mud to 30 ft - Bridge & 10 sacks of cement
at the surface.

Pipe Pulling, Inc. - Plugging Contractor
Cons. Div.

APR 24 1950

STATE CORPORATION
COMMISSIONDistrict Conservation Agent Date 4-21-50