

DISTRICT CONSERVATION AGENT'S REPORT



TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 16-18

LOCATION SE SE NE

SEC. 11 TWP. 20 RGE. 11

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 8 Lease Kowalsky

Operator Stanolind Oil & Gas Address Ellinwood, Kans

Field Silica County Barton

Total Depth 3285 Feet.

(Describe briefly the manner in which the well was plugged)

10 3/4" at 210' circulated with 200 sax cement - 6" O. D. at 3282 with 100 sax behind.

Sand to 3280' run 5 sax cement with dump bailer, pulled 1800' 6" casing, mudded hole to 205', set plug, rock bridge and 20 sax cement, filled with heavy mud to 30', set rock bridge and 10 sax cement to bottom cellar.

PLUGGING
FILE SEC 11 T 20 R 11W
BOOK PAGE 16 LINE 18

REC'D
Conservation
7-26-50
10 2 050
[Signature]
District Conservation Agent
Date 7-25-50
COMM. KANS.