

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15.009.14324.0000

LEASE NAME Panning #3

WELL NUMBER \_\_\_\_\_

SPOT LOCATION NW NW SE  
SE NE SE

SEC. 3 TWP. 20 RGE. 11 (E) or (W)

COUNTY Barton

Date Well Completed \_\_\_\_\_

Plugging Commenced 3/30/84

Plugging Completed 3/30/84

LEASE OPERATOR Bergman Oil Co.

ADDRESS 520 Union Center, Wichita, Ks. 67202

PHONE # ( ) 792-2263 OPERATORS LICENSE NO. # 5339

Character of Well \_\_\_\_\_  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? \_\_\_\_\_

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3301'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				10"	154'	none
				5 1/2"	3301'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet each set.

Plug Job Only - No Pipe Recovery. Pumped 125 sacks cement down 10" surface pipe & 125 sacks down 5 1/2" oil string.

Plugging complete

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 3rd day of April, 1984

Irene Hoover  
Notary Public

RECEIVED  
STATE CORPORATION COMMISSION  
4-5-84  
APR 05 1984  
CONSERVATION DIVISION  
Wichita, Kansas  
My Commission expires: \_\_\_\_\_



Bergman

15.009.14324.0000

W E L L L O G

COMPANY: Jay Bergman Oil Company  
CONTRACTOR: Pabco Drilling, Inc.

LOCATION: Sec 3 T20 R11  
SE NE SE

FARM NAME: Panning #3

COUNTY: Barton  
Kansas

COMMENCED: 3-31-49  
COMPLETED: 4-7-49  
TOTAL DEPTH: 3301'

CASING USED:

10" 154' Cem w 175 sx  
5-1/2" 3301' Cem w 75 sx

Figures Indicate Bottom of Formation

Sand	70
Sand & Shale	154
Shale & Red Bed	380
Shale & Red Bed	490
Anhydrite	520
Shale & Red Bed	1010
Shale & Red Bed	1025
Salt	1290
Shale & Shells	1405
Lime & Shale	1610
Lime	1760
Lime & Shale	1880
Shale & Lime	2115
Shale & Lime	2350
Shale & Lime	2555
Shale & Lime	2625
Lime	2690
Lime	2765
Lime & Shale	2840
Lime & Shale	2930
Lime & Shale	3035
Lime	3085
Lime	3205
Lime	3270
Shale & Lime	3301

*Open Hole Completed*

*T.D. 3310*

*Cement. DO NOT PULL PRT*