

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas, 67202

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Barton SEC. 3 TWP. 20s RGE. 11w E/W
Location as in quarters or footage from lines:
SE NW SE

Locate Well
correctly on above
Section Platt.

Lease Owner Bergman Oil Co.
Lease Name Panning #6 Well No. _____
Office Address 520 Union Center, Wichita, Ks. 67202
Character of Well (Completed as Oil, Gas or Dry Hole): _____
Date Well Completed _____
Application for plugging filed _____
Plugging commenced 11/5/83
Plugging completed 12/13/83
Reason for abandonment of well or producing formation _____

Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Marion Schmidt

Producing formation _____ Depth to top _____ bottom T.D. 3304'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	165'	none
				5 1/2"	3303'	1497'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Dumped 5 sacks cement on bottom, 50' of sand & 5 sacks cement. Shot pipe at 2810'
2530', 1825', & 1497'. Pulled total of 46 joints of 5 1/2". Plugged well with
4 hulls, 25 cement, 12 gel, 40 cement, 3 gel, 1 hull, plug, & 100 sacks 50/50
poz 6% gel 3% c.c.

Plugging complete.

(If additional description is necessary, use BACK of this sheet)


Name of Plugging Contractor Kelsó Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Box 347, Chase, Ks. 67524
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of December, 1983



Irene Hoover
Notary Public.

My Commission expires: _____
STATE CORPORATION COMMISSION

DEC 16 1983 12-16-83

107.39

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas


15.009.14327.0000

Company- JAY BERGMAN OIL
 Farm- Panning No. 6

SEC. 3 T. 20 R. 11W
 SE NW SE

Total Depth. 3304'
 Comm. 11-19-52 Comp. 12-10-52
 Shot or Treated.
 Contractor.
 Issued. 7-28-56

County Barton
 KANSAS



CASING:
 8 5/8" 165' cem w/150 sx
 5 1/2" 3303' cem w/75 sx

Elevation. 1764' DE

Production. 40 BO & NW

Figures indicate Bottom of Formations

NO LOG AVAILABLE

- 3061-68 limestone cream, fine crystalline, partly oolitic, poor porosity, trace light spotted stain, faint odor, no free oil.
 3124-40 limestone gray, fine crystalline, oolitic and oolitic, fair to good porosity, no saturation, no odor.
 3222-26 limestone gray, medium crystalline, oolitic, good porosity, no saturation, no odor.
 3293-98 limestone tan, fine crystalline, shaley, partly oolitic and oolitic, poor to fair porosity, spotted saturation and good odor.
 3301-04 dolomite tan, soft, fine to medium crystalline, poor porosity, light saturation, good odor, show of free oil.

Total Depth

Tops:	
Anhydrite	500
Heebner	2898
Brown Lime	3023
Lansing	3044
Arbuckle	3301