


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Barton County. Sec. 3 Twp. 20 Rge. (E) 11 (W)

Location as "NE/CNW/SW" or footage from lines SW NE SW  
Lease Owner Jay Bergman Oil Company  
Lease Name Schmidt Well No. #3  
Office Address 425 Union Center Building Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed March 1 19 59  
Application for plugging filed March 1 19 59  
Application for plugging approved March 1 19 59  
Plugging commenced March 1 19 59  
Plugging completed 1:00 PM March 1 19 59  
Reason for abandonment of well or producing formation \_\_\_\_\_

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Don Truan  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3346 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mud to 210' 1/2 sacks hulls, plug and 25 sacks cement thru drill pipe. Mud to 40' 1/2 sack hulls plug and 10 sacks cement to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

3-7-59 MAR 7 1959

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Jay Bergman Oil Company  
Address 425 Union Center Building Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Harold Bergman (employee of owner) (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Harold Bergman  
425 Union Center Building Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 3 day of March 19 59  
Judith L. Palmer  
Notary Public.

My commission expires October 15, 1962

PLUGGING  
FILE SEC 3 T. 20 R. 11W  
BOOK PAGE 22 LINE 44

WELL LOG

15.009.07011.0000

Date Started: February 17, 1959  
Date Completed: March 1, 1959

#3 Schmidt  
SW NE SW, Sec. 3-T20s-R11w  
Barton County, Kansas

*Gay Bergman Oil*

- 0-198 Sand Clay and Shale
- 198-511 Red Bed Sand and Shale
- 511-531 Anhydrite
- 531-875 Red Bed Shale
- 875-1385 Shale and Shells
- 1385-1490 Shale and Lime
- 1491-1600 Lime
- 1600-2120 Lime and Shale
- 2120-2415 Shale and Shells
- 2415-2685 Shale and Lime
- 2685-2922 Lime
- 2922-3008 Shale and Shells
- 3008-3080 Lime and Shale
- 3080-3310 Lime
- 3310-3345 Shale and Conglomerate
- 3345 RTD

- Elevation 1770 KB
- Anhydrite 511 (-1259) Drillers top
- Heebner Shale 2912 (-1142)
- Douglas Section 2946 (-1176)
- Brown Lime 3041 (-1271)
- Lansigg KC 3036 (-1290)
- Conglomerate 3320 (-1550)
- RTD 3345 (-1575)

**RECEIVED**  
STATE CORPORATION COMMISSION  
MAR 7 1959  
REGISTRATION DIVISION  
Topeka, Kansas

AFFIDAVIT

State of Kansas.....Sedgwick County

I, Do swear that the statements and matter herein contained are true to the best of my knowledge.

BERGMAN DRILLING, INC.

*Harold Bergman*  
\_\_\_\_\_  
Harold Bergman

Subscribed and sworn before me this \_\_\_\_\_ day of March, 1959

My commission Expires October 15, 1962

*Judith L. Palmer*  
\_\_\_\_\_  
Notary Public

PLUGGING  
FILE SEC 3 T. 20 R. 11W  
BOOK PAGE 22 LINE 44