

R

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

WELL PLUGGING RECORD

McPherson County, Sec. 6 Twp. 19 Rge. (E) 1 (W)

Location as "NE/CNW%SW%" or footage from lines NE SW SW

Lease Owner Colorado Oil and Gas Corporation

Lease Name RUSSELL Well No. 2

Office Address Box 1030, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Oil

Date well completed 3-7 19 45

Application for plugging filed 10-30 19 59

Application for plugging approved 11-2 19 59

Plugging commenced 11-20 19 59

Plugging completed 11-30 19 59

Reason for abandonment of well or producing formation Producing zone depleted

If a producing well is abandoned, date of last production 10-30 19 59

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Jones

Producing formation Mississippian Depth to top 2941 Bottom Total Depth of Well 2976 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	157'	None
				5-1/2"	2948'	1505'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled back to 2930'. Dumped 5 sacks of cement. Shot pipe off at 1505'. Pulled pipe and mudded hole to 180'. Set rock bridge and dumped 15 sacks of cement. Finished mudding hole to 40'. Set another rock bridge and dumped 8 sacks of cement at base of cellar.

12-23-59  
RECEIVED  
STATE CORPORATION COMMISSION  
DEC 23 1959  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Bert Self Casing Pulling Co.

Address R.R. #4, Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Bill K. Henrichs

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Bill K. Henrichs  
Box 1030, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 22nd day of December, 1959

My commission expires August 19, 1963

Helen L. Martin  
Helen L. Martin Notary Public.



THE DERBY OIL COMPANY  
WELL RECORD  
PRODUCTION DEPARTMENT

15-113-02268-00-00  
**RECEIVED**  
STATE CORPORATION COMMISSION

NOV 2 1959

CONSERVATION DIVISION  
Wichita, Kansas

SUBSEQUENT OPERATION NO. 1

LEASE Russell WELL NO. 2  
RECORD COMPILED August 27, 19 51 BY W. Clements  
LOCATION NE SW SW SEC. 6 TWP. 19 RGE. 1W  
COUNTY McPherson STATE Kansas  
ELEVATION GROUND \_\_\_\_\_ D.F.: 1562 K.B.: 1564  
ALL MEASUREMENTS ARE FROM Derrick Floor WHICH WAS -- FT. ABOVE --  
CONTRACTOR E. K. Carey  
OPERATION COMMENCED: 12-13-48 OPERATION COMPLETED 12-19-48  
PURPOSE OF OPERATION To clean out hole and drill deeper to increase production.  
  
DAILY PRODUCTION TEST BEFORE OPERATION 3 BBLs. OIL 3 BBLs. WATER: DATE 10-20-48  
DAILY PRODUCTION TEST AFTER OPERATION 2½ BBLs. OIL 1 BBLs. WATER: DATE 5-13-49  
TOTAL DEPTH BEFORE OPERATION 2962 AFTER OPERATION 2976  
RESULTS OF OPERATION No increase in fluid.

DETAILED DESCRIPTION OF OPERATION:

Pulled tubing and rods. Bailed hole to bottom. Drilled deeper to 2976 total depth. Swabbed and bailed hole dry. Dumped 150 gallons clean water in hole, then 100 pounds of Kem-I-Kal. Ran swab and bailer. Swabbed hole down. Washed hole with clear water. No increase in fluid. Ran tubing & rods.

THE DERBY OIL COMPANY

RECEIVED  
STATE CORPORATION COMMISSION

NOV 2 1950

Record of Well No. 2  
Location: NE SW SW  
Contractor: E. K. Carey  
Drilling Commenced: 2-4-45  
Elevation: 1562

Farm: Russel  
Sec. 6 Twp. 19 Rge. 17  
County: McPherson  
State: Kansas  
Drilling Completed: 3-7-45

CONSERVATION DIVISION  
Wichita, Kansas

CASING RECORD

size	feet	kind	weight
10 3/4"	157'		32.75#
5 1/2"	2948'	OD	

100 sacks Cem. By Halliburton  
100 sacks bulk cement

Formation	Bottom	Formation	Bottom
Sand & Shale	0- 75		
Shale & Shells	157		
Lime & Shale	798		
Lime	905		
Lime & Sand	960		
Shale & Shells	1785		
Lime	2184		
Sand	2225		
Lime & Shale	2351		
Lime	2541		
Lime & Shale	2595		
Lime	2695		
Shale & Lime	2943		
Chat	2962		

GEOLOGICAL SURVEY

Tops:  
Lans. 2325'  
ML 2941'  
Total Depth 2962'

Light odor and sat. 2950-52. DP Pay  
2956-62 TD 850' oil plus 150' wtr. 16 hrs.  
Swab 1 1/4" BO plus s.w. Hr. 3 hrs. 1000A.  
Swab 3 1/2" BO plus 1 EWPH 6 hrs. Est.  
75 BO plus 24 BW