

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

McPherson County, Sec. 6 Twp. 19 Rge. 1 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SW SE NW

Lease Owner C.V. Phillips

Lease Name Ryno #2 Well No.

Office Address Hutchinson, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19

Plugging commenced 11-1-57 19

Plugging completed 11-2-57 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Ruel Durkee

Producing formation Depth to top Bottom Total Depth of Well 2948 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	185'	none
				5-1/2"	2940'	706'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pulled 5 1/2" casing, mudded the hole to 185', set a 10' rock bridge and ran 15 sacks of cement. Mudded the hole from 130' to 25', set a 10' rock bridge to 15' and ran 5 sacks of cement to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor West Supply Co., Inc.

Address Chase, Kansas

STATE OF Kansas, COUNTY OF Reno, ss.

C.V. Phillips (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C.V. Phillips

Hutchinson, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 14th day of November, 1957

My commission expires November 16, 1957 Edilma A. Clark - Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

NOV 15 1957 11-15-57

CONSERVATION DIVISION
Wichita, Kansas


PLUGGING
FILE SEC. 6 T. 19 R. 1W
BOOK PAGE 58 LINE 21

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
412 Union National Bldg., Wichita, Kansas

Company - BAY PETRO. CORP. & WESTGATE-GREENLAND SEC. 6 7. 19 R. 1 W
Farm - Ryno No. 2. SW SE NW

Total Depth. 2948 DFM
Comm. 5-28-45 Comp. 8-17-45
Shot or Treated.
Contractor. C.C. Nelson Drlg. Co.
Issued. 9-29-45

County. McPherson
KANSAS



CASING:
8 5/8" 185' Cem. 100 SFX
5 1/2" 2940' Cem. 100 SFX

Elevation. _____

Production. Pot. 273 BO & 16% Wtr.

Figures indicate Bottom of Formations.

surface sand	0-185
shale & shells	395
lime & shale	820
lime sdy	900
lime & shale	1000
sand & shale	1100
shale, lime & shells	1340
shale & shells	1410
lime sdy	1480
shale & shells	1650
lime & shale	1980
lime	2075
lime & shale	2230
lime	2360
lime brkn	2480
lime	2665
lime & shale	2920
lime & sand	2930
lime cherty	2943
chat	2950
Total Depth	2948 DFM

Tops:
'Tarkio 1399
'Lansing 2316
'Mississippi 2915
'T.D. Derrick Floor 2948

'Acidized w/500 gals @ 2947
'Acidized w/1000 gals @ 2950
'Swbd 25 BOPH
'Pot. 273 BOPD - 16% Wtr.

RECEIVED
CORPORATION COMMISSION
NOV 1 1957
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 6 T. 19 R. 1W
BOOK PAGE 50 LINE 21