

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

January 6, 1979

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JAN 17 1979
1-17-79
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Harry Hughes of Triangle Drilling of Ft. Dodge has this date requested permission to plug the following described well:

Mr. Hughes guarantees payment of the plugging fee.

Operator's full Name: Decker Petroleum, Inc.

Complete Address: P.O. Box 152, Canton, Kansas 67428

Lease Name: Fisher Well No. 1

Location: JW SW SE Sec. 1 Twp. 19 Rge. 1 (E)(W) X

County: McPherson Total Depth 2889' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Hughes was instructed to plug the well as follows:

8 5/8" - 140' - 85 sacks. Fill hole with mud to 135'. Push plug and 1/2 sack hulls to 135' and cement hole with 20 sacks cement. Fill hole with mud to 40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks cement. Bridge rathole and cement with 2 sacks.

Very truly yours,

Stephen J. Larson
Conservation Division Agent