



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAY 7 - 1974
5-7-74
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Wayne Kirkman of Wayne Kirkman Oil Company has this
date requested permission to plug the following described well:

Mr. Wayne Kirkman guarantees payment of the plugging fee.

Operator's full Name: Wayne Kirkman Oil Company

Complete Address: 1901 Cottonwood, Great Bend, Kansas 67530

Lease Name: O. Soeken Well No. # 2

Location: C W/2 SW SW ^{NE} Sec. 5 Twp. 20 Rge. 11 (E)(W) W

County: Barton Total Depth 3316 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Russ Sullivan was instructed to plug the well as follows:

8 5/8" csg. 203' Cwc.

Mixed & pumped 5 sax mud & 20 sax cement down to 2600'. Pulled pipe.

Squeezed well with 20 sax mud, 2 sax hulls, & 100 sax cement with

Allied Cementing Company's pump truck, cementing from 320' to base

of cellar.

Very truly yours,

Don L. Lusk
Conservation Division Agent