



15.009.21494.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Cameran of Big Springs Drlg. has this

date requested permission to plug the following described well:

Mr. Cameran guarantees payment of the plugging fee.

Operator's full Name: Tomlinson Oil Co., Inc.

Complete Address: 200 W. Douglas, Wichita, Ks.

Lease Name: Gene Well No. 1

Location: C SW SE Sec. 4 Twp. 20 Rge. (E)(W) 11

County: Barton Total Depth 3358' Oil Well

Gas Well Input Well SWD Well D & AXX Lost Hole

Mr. Cameran was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 40 sk cmt plug at 420' thru drill pipe.

Heavy mud to 210' set 25 sk cmt plug thru drill pipe. Heavy mud to 40'

set solid bridge & 10 sk cmt plug to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

NOV 27 1978

Very truly yours,

CONSERVATION DIVISION
Wichita, Kansas

11-27-78

Leo Massey
Conservation Division Agent