

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION

10-29-62  
 OCT 29 1962

CONSERVATION DIVISION  
 Wichita, Kansas

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

Dear Sir:

Mr. G. A. Reynolds of Pan American Pet. Corp. has this  
 date requested permission to plug the following described well:

Mr. G. A. Reynolds guarantees payment of the plugging fee.

Operator's full Name: Pan American Petroleum Corp.

Complete Address: Box 1654, Oklahoma City, Oklahoma

Lease Name: Panning Well No. 19

Location: G NE SE Sec. 10 Twp. 20 Rge. 11 (E) (W)

County Barton Total Depth 3286 Oil Well X

Gas Well    Input Well    SWD Well    D & A    Lost Hole   

Mr. Noel Knight was instructed to plug the well as follows:

8 5/8" 211' Cwc.

Sanded hole back to 3265' & dumped 4 sax cement with dump  
 bailer. Pulled pipe, to 400' & circulated hole with mud.

Pulled pipe to 200' & displaced 25 sax cement thru pipe.

Completed pulling pipe, set rock bridge @ 40' & displaced  
 10 sax cement, cementing to base of cellar.

Very truly yours,

Don Truss  
 Conservation Division Agent