


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barton

County. Sec. 11 Twp. 20S Rge. 11W (EX) (W)

Location as "NE/CNW/SW" or footage from lines Appr. NE NW NE
Lease Owner Kansas Petroleum, Incorporated
Lease Name Kowalsky #1 Well No.
Office Address 1620 Wichita Plaza, Wichita, Kansas 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 24, 1971 19
Application for plugging filed December 23, 1971 19
Application for plugging approved December 23, 1971 19
Plugging commenced 11:00 PM, December 23, 1971 19
Plugging completed 1:30 AM, December 24, 1971 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truman
Producing formation Depth to top Bottom Total Depth of Well 3330 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	215'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud to 480', spotted 40 sacks
through drill pipe at 480'. Heavy
mud to 200', spotted 25 sacks through
drill pipe at 200'. Heavy mud to 40'
with 1/4 sack hulls and Howco plug
at 40' with 10 sacks to surface.

1-3-72

RECEIVED
STATE CORPORATION COMMISSION
JAN 3 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor STERLING DRILLING COMPANY
Address P. O. Box 129, Sterling, Kansas 67579

STATE OF Kansas, COUNTY OF Rice, ss.

Bernard Laudermilk, Asst. Secretary (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. STERLING DRILLING COMPANY

(Signature) Bernard Laudermilk
Bernard Laudermilk, Asst. Secretary
P. O. Box 129, Sterling, Kansas 67579
(Address)

Subscribed and sworn to before me this 28th day of December, 1971.

CHARLES M. HALL—NOTARY PUBLIC
My Commission Expires Jan. 6, 1974

Notary Public.

15.009.20647.0000

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

WELL LOG - - - - - KOWALSKY #1
Located: Appr. NE NW NE, Sec. 11-20S-11W, Barton County,
Kansas

OWNER: Kansas Petroleum, Incorporated
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: December 14, 1971
COMPLETED: December 24, 1971

TOTAL DEPTH: 3330'

LOG

0 - 72	Sand and Gravel
72 - 100	Clay and Shale
100 - 215	Sand, Clay, Shale
215 - 1226	Shale
1226 - 2564	Shale and Lime
2564 - 2840	Lime
2840 - 3050	Lime and Shale
3050 - 3270	Lime
3270 - 3285	Lime and Shale
3285 - 3330	Lime

CASING RECORD

Ran 5 joints 8 5/8" 20# surface casing,
203' cemented at 215' K.B. with 200
sacks 60/40 Pozmix 3% HA-5. Plug down
at 8:05 PM, 12-14-71.

Plugged.

RECEIVED
STATE CORPORATION COMMISSION
JAN 3 1972
CONSERVATION DIVISION
Wichita, Kansas