


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Barton County. Sec. 12 Twp. 16S Rge. (of 13) W
Location as "NE/CNW%SW%" or footage from lines 1650' fr. N, and 1650' fr. W, NW/4
Lease Owner Phillips Petroleum Company
Lease Name Allen Well No. 2
Office Address Box 779, Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 18, 19 57
Application for plugging filed October 18, 19 57
Application for plugging approved October 18, (verbally) 19 57
Plugging commenced October 18, 19 57
Plugging completed October 18, 19 57
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production - 19 -
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well _____
Producing formation Dry Hole Depth to top - Bottom - Total Depth of Well 3457 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Heebner	Dry	3035	3052	9-5/8"	625.59	None
Toronto	Dry	3052	3066			
Douglas	Dry	3066	3122			
Brown Lime	Dry	3122	3132			
LKC	Dry	3132	NR			
Drum	Dry	3266	NR			
Conglomerate	Dry	3377	NR			
Arbuckle	Dry	3440	3457			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Mudded hole from 3457' to 300'. Dumped 1/3 sx. hulls and set Howco bridge plug. Spotted 25 sx. cement 300' to 237'. Mudded 237' to 30'. Dumped 1/3 sx. hulls and set Howco bridge plug at 30'. Dumped 10 sx. cement in filling to base of cellar. Well plugged and abandoned 1:30 P.M. 10-18-57.

10-23-57

RECEIVED
STATE CORPORATION COMMISSION
OCT 23 1957
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Halliburton Oil Well Cementing Company
Address Duncan, Oklahoma

STATE OF Kansas, COUNTY OF Barton, ss.
A. J. Willis (employee of owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

Box 779, Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 21st day of October, 19 57

My commission expires 11-18-57

Notary Public.

PLUGGING
FILE SEC 12 T. 16 R. 13W
BOOK PAGE 55 LINE 9

15-009-05 028-0000

EXPLORATION RECORD

Phillips Petroleum Co.

Allen #2 - 1650' from North and 1650' from West Lines, NW/4 Sec. 12-16S-13W,
Barton County, Kansas - Dry Hole

Lease Allen

Well 2

Formation Name	Top	Base	Remarks
Surface soil and sand	0	70	
Shale and shells	70	525	
Shale and redbed	525	630	
Redbed and shells	630	825	
Anhydrite	825	853	
Iron	853	890	
Shale and shells	890	1605	
Lime and shale	1605	2809	
Lime	2809	3410	
Lime and shale	3410	3457	
<u>FORMATION TOPS:</u>			
Heebner	3035		
Toronto	3052		
Douglas	3066		
Brown Lime	3122		
Lansing-Kansas City	3132		
Drum	3266		
Conglomerate	3377		
Arbuckle	3440		
Rotary T.D.	3457		
Dry Hole - P & A 10-18-57			

PLUGGING
 FILE SEC. 12 T. 16 R. 13W
 BOOK PAGE 55 LINE 9

RECEIVED
 PROPERTY DIVISION
 OCT 25 1957
 CONSERVATION DIVISION
 W. 12th, Kansas