


15-009-05172-000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Barton County. Sec. 12 Twp. 163 Rge. 13 (E) W (W)
Location as "NE/CNWxSWx" or footage from lines NW NE SE
Lease Owner Fred J. Haynes
Lease Name Whitmer Well No. 3
Office Address Bldg. & Loan Bldg., Russell, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 28 19 60
Application for plugging filed May 28 19 60
Application for plugging approved May 28 19 60
Plugging commenced May 28 19 60
Plugging completed May 28 19 60
Reason for abandonment of well or producing formation _____



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? Yes

Name of Conservation Agent who supervised plugging of this well Don Truan
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3391 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	320'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled hole with mud to 300' - set # 1 plug at 300' and cemented with 1/4 sack hulls and 20 sacks cement - set # 2 plug at 35' and cemented with 10 sacks cement.

6-10-60
RECEIVED
STATE CORPORATION COMMISSION
JUN 10 1960
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Haynes Drilling Company
Address Russell, Kansas

STATE OF Kansas, COUNTY OF Russell, ss.
Darrell E. Haynes (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Darrell E. Haynes
Bldg. & Loan Bldg., Russell, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of June, 19 60
Ralph L. Schutte
Notary Public.

My commission expires January 17, 1961.



DRILLERS LOG

Whitmer # 3

NW NE SE 12-16-13

Barton County, Kansas

OPERATOR: Fred J. Haynes.
Bldg. & Loan Bldg.
Russell, Kansas

CONTRACTOR: Haynes Drilling Company
Russell, Kansas

COMMENCED: May 18, 1960

COMPLETED: May 28, 1960 CASING: 8 5/8" at 320'w/150sks

I. P. - D & A

Tops:	Anhydrite	864	
	Heebner	3025	-1114
	Lsg.-KC	3122	-1211
	Cong	3375	-1464
	Arbuckle	3387	-1476

FORMATION:

Surface Clay & Rock	35
Shale & Shells	319
Shale & Sand	510
Red Bed	864
Anhydrite	864-890
Shale & Shells	1060
Salt & Shale	1200
Shale & Lime	1655
Lime & Shale	2570
Lime	2880
Lime & Shale	3065
Lime	3335
Conglomerate	3385
Arbuckle & TD	3391

RECEIVED
STATE CORPORATION COMMISSION

JUN 10 1960

CONSERVATION DIVISION
Wichita, Kansas

I certify that the above is true and correct
to the best of my knowledge.

Samuel E. Haynes