

*R*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 36-31

LOCATION NE-SE-NE

SEC. 11 TWP. 10 RGE. 11-w

Dry Hole \_\_\_\_\_ Abandoned Oil Well X Abandoned Gas Well \_\_\_\_\_

I have today completed supervision of plugging of:

Well No. 7 Lease Howalsky

Operator Standard Oil & Gas Co Address Box #7 - Elliswood - Kans.

Field \_\_\_\_\_ County Barton

Total Depth 3288 Feet.

(Describe briefly the manner in which the well was plugged)

*Surface Pipe 10 3/4 - 225 ft. Circulated with cement  
6 casing set at 3276 ft Cemented with 100 sacks cement  
Plugged back to 3270 ft with chat - Washed 6 sacks  
of cement at 3270 ft - Shot off & pulled the 6 casing  
head to 225 ft. Set Rock Bridge & 20 sacks of cement  
at 225 ft. Head to 30 ft. Bridge & 10 sacks of  
cement at the surface  
West Supply Co. - Plugging Contractors -*

**RECEIVED**  
STATE CORPORATION COMMISSION  
NOV 13 1950  
11-13-50

*W. D. Stough*  
District Conservation Agent

Date 11-11-50

**PLUGGING**  
FILE SEC. 11 T. 10 R. 11W  
BOOK PAGE 36 LINE 31