

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 36-34

LOCATION NW-SE-SE

SEC. 11 TWP. 20 RGE. 11-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 11 Lease Stueckmann-A

Operator Standard Oil & Gas Address Box #7 Elliswood-Kans.

Field _____ County Barton

Total Depth 3287 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2" - 221 ft. Circulated with cement
5/8" casing set at 3249 ft. Cemented with 25 sacks cement
Filled back to 3270 ft with chat - Dumped 5 sacks
of cement at 3270 ft. Ripped off & pulled the
8 1/2" casing - Mud to 221 ft - Set Back Bridge &
15 sacks of cement at 221 ft. Mud to 30 ft. Bridge
& 10 sacks of cement at the surface -
R. S. Plugging Co. Plugging Contractors

RECEIVED
STATE CORPORATION COMMISSION
PLUGGING
NOV 14 1950
FILE SEC. 11 TWP. 20 RGE. 11-W
BOOK PAGE 38 LINE 34
CONSERVATION DIVISION

C. D. Stough -
District Conservation Agent
Date 11-12-50

11-14-50