

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 36-35

LOCATION C5/2 - 22 1/2 - SE 1/4

SEC. 11 TWP. 20 RGE. 11-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 8 Lease Stueckmann, S.

Operator Stanliud Oil & Gas Co Address Box #7 - Elkhartwood - Kansas

Field _____ County Barton

Total Depth 3280 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4 - 209 ft. Circulated with cement.
5/8 casing at 3270 ft. Cemented with 125 sacks cement
Plugged back to 3260 ft. with cement - Dumped 5 sacks
of cement at 3260 ft. - Milled off & Pulled the 5/8 casing -
Mud to 209 ft. - Set Rock Bridge x 20 sacks of cement
at 209 ft. - Mud to 30 ft. - Plug x 10 sacks of cement
at the surface.

A. & S. Pipe Pulling Co. - Plugging Contractors

PLUGGING
FILE SEC. 11 TWP. 20 RGE. 11W
BOOK PAGE 36 LINE 35

RECEIVED
NOV 10 1950
C. M. Stover
District Conservation Agent

Date 11-7-50