

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 66-43LOCATION NE-21E-2ESEC. 11 TWP. 20 RGE. 11-WDry Hole Abandoned Oil Well X Abandoned Gas Well

I have today completed supervision of plugging of:

Well No. 3 Lease P. HowelskyOperator Stanford Oil & Gas Co Address Box #9, Ellinwood - Kans.Field County BartonTotal Depth 3311 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 13'- 188ft. Circulated with cement.
7" casing set at 3279ft. Cemented with 100 sacks of
Cement - Plugged back to 3270ft. with shot. Dumped
6 sacks of cement at 3270ft. - Shot off & pulled the
7" casing. - mud to 188ft. - Set Rock Bridge & 25 sacks
of cement at 188ft. - mud to 30ft. Bridge &
10 sacks of cement at the surface.
West Supply Co. - Plugging Contractors

STATE CORPORATION COMMISSION

MAR 26 1951

CONSERVATION DIVISION
Wichita, KansasC. M. Stough
District Conservation AgentDate 3-12-51