

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 66-42

LOCATION NW-27W-SE

SEC. 11 TWP. 20 RGE. 11-W

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 2 Lease G. Streckman

Operator Standard Oil Co Address Box #7 Ellinwood-Kans.

Field _____ County Barton

Total Depth 3295 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4 - 229 ft. Circulated with cement.
6" casing set at 3289 ft. Cemented with 100 sacks cement.
Plugged back to 3280 ft with chat - Mixed
5 sacks of cement at 3280 ft. Shot off. Pulled the
6" casing - Mud to 229 ft. Set Rock Bridge &
20 sacks of cement at 229 ft. Mud to 30 ft.
Plug & 10 sacks of cement at the surface.
Wheat Supply Co. Plugging Contractors

RECEIVED
PLUGGING DISTRICT CONSERVATION COMMISSION
FILE SEC. 11 TWP. 20 RGE. 11-W 1951
BOOK PAGE 46 DATE 3-30-51
DISTRICT CONSERVATION DIVISION
Wichita, Kansas
C. M. Stouck
District Conservation Agent

4-3-51