

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 176-32

LOCATION C7/2-7/2-SE

SEC. 11 TWP. 20 RGE. 11-00

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 6 Lease G. Stueckemann

Operator Stanolind Oil & Gas Co. Address Box #1654 Okla City - Okla.

Field _____ County Barton

Total Depth 3284 Feet. Plugging Contractor - West Supply Co #14
Chas. H. Hester

(Describe briefly the manner in which the well was plugged)

Surface Pipe 1 3/4 - 202 ft - Circulated with cement
6" casing set at 3272 ft - 100 sacks of cement - Plugged
back to 3250 with sand & chat - Dumped 5 sacks of
cement at 3250 ft - shot off & pulled the 6" casing
back to 202 ft - Set rock bridge & 25 sacks of
cement at 202 ft - mud to 30 ft - Bridge &
10 sacks of cement at the surface.

PLUGGING
FILE SEC 11 T 20 R 11W
BOOK PAGE 26 LINE 32

RECEIVED
STATE CORPORATION COMMISSION
OCT 15 1953
CONSERVATION DIVISION
Wichita, Kansas
10-15-53

C. M. Strong
District Conservation Agent
Date 10-13-53