

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 34-6LOCATION SW 1/4 - NW 1/4SEC. 11 TWP. 20 RGE. 11-WDry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 18 Lease F. PanningOperator Stanford Oil & Gas Co Address Box #7 - Ellinwood - Kans.Field _____ County BarberTotal Depth 3379 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 10 3/4 - 286 ft. Circulated with cement.
7" casing set at 3275 ft. cemented with 100 sacks cement
Plugged back to 3265 ft with chat - 6 sacks of cement
dumped at 3265 ft. Shot off & pulled the 7" casing
Filled with mud to 286 ft. Set Rock Bridge & 20 sacks
of cement at 286 ft. Mud to 30 ft. Plug &
10 sacks of cement at the surface.
West Supply Co. Plugging - Contractors

RECEIVED
STATE CORPORATION COMMISSION

NOV. 20 1950

CONSERVATION DIVISION

District Conservation Agent

Date 11-18-50

PLUGGING	
FILE	SEC <u>11</u> TWP <u>20</u> RGE <u>11-W</u>
BOOK	PAGE <u>34</u> LINE <u>6</u>