

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-025-21579-00-00  
Spot: SWNESESW Sec/Twnshp/Rge: 9-32S-21W  
667 feet from S Section Line, 3063 feet from E Section Line  
Lease Name: HARDEN Well #: 2  
County: CLARK Total Vertical Depth: 5380 feet

Operator License No.: 31691  
Op Name: CORAL COAST PETROLEUM, L.C.  
Address: 9032 E. LAKEPOINT DR  
WICHITA, KS 67226

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5215		WITH 2 SX CMT
COND	16	100		WITH 125 SX CMT
PROD	5.5	5380	0	WITH 225 SX CMT
SURF	8.625	603		WITH 175 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/26/2018 10:00 AM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Revd. from: DARON PATTERSON Company: CORAL COAST PETROLEUM Phone: (620) 539-0464

Proposed Plugging Method: CIBP at 5215 with 2 sacks cement. Pressure test casing. Perforate 5 1/2" casing at 1090' and pump 50 sack plug with hulls in last 25 sx cmt. Perforate 5 1/2" casing at 650' and circulate cement from 650' to surface.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 04/26/2018 3:30 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

SET CIBP @ 5215' WITH 2 SX CMT. PRESSURED TESTED CASING TO 500#. PERFORATE AT 1090'. RAN TBG & PUMPED 50 SX CMT WITH 50# HULLS IN LAST 25 SX. PULLED TBG. PERFORATE AT 650' & CIRCULATE CMT TO SURFACE IN & OUT 5 1/2" CASING WITH 225 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5265	5275		
<i>Favorable 7-2018</i>			

Remarks: USED 60/40 POZMIX 4% GEL BY HURRICANE SERVICES.

Plugged through: TBG

District: 01

Signed

Larry Harris - ECR 5  
(TECHNICIAN)

RECEIVED  
MAY - 7 2018  
KCC DODGE CITY

*MD*

*SR*