

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-073-01256-00-00
Spot: NWNESES Sec/Twnshp/Rge: 2-26S-8E
1200 feet from S Section Line, 3140 feet from E Section Line
Lease Name: STEVENSON Well #: W-5
County: GREENWOOD Total Vertical Depth: 2345 feet

Operator License No.: 5394
Op Name: ABDERHALDEN, R. R.
Address: 100 S. MAIN, STE 510
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2334		50 SX
SURF	8.63	83		15 SX

Well Type: EOR UIC Docket No: _____ Date/Time to Plug: 06/04/2018 10:00 AM
Plug Co. License No.: 5656 Plug Co. Name: R.R.A., INC.
Proposal Revd. from: DARYL WHITEMAN Company: _____ Phone: (316) 640-9072

Proposed Plugging Method: Set a 50 ft cement plug at TD. Mud to 1000 ft. Shoot off pipe at 1000 ft. Pull pipe. Set a 50 ft cement plug at 1000 ft. Pull tubing to 150 ft. and cement to surface.

Plugging Proposal Received By: MICHAEL HEFFERN WitnessType: PARTIAL
Date/Time Plugging Completed: 06/04/2018 2:00 PM KCC Agent: MICHAEL HEFFERN

Actual Plugging Report:

Ran tubing to 1500', iron in hole below 1500' not able to remove, pumped 20 sxs cement, @ 1500', pulled pipe to 1010', pumped 15 sxs cement, pulled tubing to 150' pumped 80 sxs cement, gel spacers between cement plugs, casing shot @ 1010' & 150'.

Perfs:

RECEIVED
KCC DIST # 3
JUN 11 2018
CHANUTE, KS

mt

INVOICED

JUL 12 2018

Remarks:

Plugged through: TBG

District: 03

Signed Mike Deffen
(TECHNICIAN)