

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-205-23295-00-00  
Spot: SESWNWNE Sec/Twnshp/Rge: 4-27S-15E  
1017 feet from N Section Line, 2304 feet from E Section Line  
Lease Name: CLINESMITH Well #: 2-4  
County: WILSON Total Vertical Depth: 1500 feet

Operator License No.: 35341  
Op Name: RIVER ROCK OPERATING, LLC  
Address: 211 N. ROBINSON SUITE 200  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1475		230 SX
SURF	7	160		83 SX

Well Type: CM UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/19/2018 10:00 AM  
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC  
Proposal Revd. from: JORDAN JAMISON Company: ALAN DUNNING Phone: (620) 432-4200

Proposed Plugging Method: Circulate cement through tubing from TD to surface plus 10%. Top off cement at surface as needed. Cut off production casing 5ft below ground level. Reclaim location to original topography.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE  
Date/Time Plugging Completed: 06/19/2018 10:00 AM KCC Agent: ALAN DUNNING

Actual Plugging Report:

Perfs:

A cement string was lowered to TD and the well pumped full of cement from btm to top. The cement string was pulled to 200 ft and the well again pumped full of cement. The cement string was removed and the well topped off with cement. According to operator, a total of 126 sacks of portland cement were used to plug well. The wellhead was cut off below plow depth and the location restored.

RECEIVED  
KCC DIST # 3  
JUL 13 2018  
CHANUTE, KS  
AD

INVOICED  
JUL 20 2018

Remarks:

Plugged through: CSG

District: 03

Signed Alan Dunning  
(TECHNICIAN)