

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-099-24405-00-00  
Spot: SWNENWNE Sec/Twnshp/Rge: 16-31S-19E  
4632 feet from S Section Line, 1917 feet from E Section Line  
Lease Name: KATHERINE J. BILLER TRUST Well #: 16-1  
County: LABETTE Total Vertical Depth: 930 feet

Operator License No.: 35341  
Op Name: RIVER ROCK OPERATING, LLC  
Address: 211 N. ROBINSON SUITE 200  
OKLAHOMA CITY, OK 73102

| String | Size  | Depth (ft) | Pulled (ft) | Comments |
|--------|-------|------------|-------------|----------|
| PROD   | 5.5   | 930        |             | 125 SX   |
| SURF   | 8.625 | 20         |             | 5 SX     |
| T1     | 2.375 | 797        |             |          |

Well Type: CM UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/26/2018 12:00 AM  
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC  
Proposal Rcvd. from: JORDAN JAMISON Company: \_\_\_\_\_ Phone: (620) 432-4200

Proposed Plugging Method: Circulate cement through tubing from TD to surface plus 10%. Top off cement at surface as needed. Cut off production casing 5ft below ground level. Reclaim location to original topography.

Plugging Proposal Received By: \_\_\_\_\_ WitnessType: NONE  
Date/Time Plugging Completed: 06/26/2018 12:00 AM KCC Agent: RUSSELL HINE

Actual Plugging Report:

Circulate cement through tubing to surface. Pull tubing up to 200', pump 18 bbls. Top off cement at surface as needed. Cut off production casing 5ft below ground level. Reclaim location to original topography. 126 Total sacks cement pumped.

Perfs:

| Top | Bot | Thru | Comments |
|-----|-----|------|----------|
| 755 | 757 |      |          |
| 748 | 750 |      |          |
| 598 | 600 |      |          |
| 537 | 539 |      |          |
| 522 | 524 |      |          |
| 372 | 376 |      |          |
| 354 | 358 |      |          |

RECEIVED  
KCC DIST # 3  
JUL 17 2018  
CHANUTE, KS

RH

INVOICED

JUL 20 2018

Remarks:

Plugged through: TBG

District: 03

Signed Russell Hine  
(TECHNICIAN)