

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-133-26225-00-00
Spot: SWNESE Sec/Twnshp/Rge: 32-29S-19E
2155 feet from S Section Line, 659 feet from E Section Line
Lease Name: WHITE FARMS Well #: 32-1
County: NEOSHO Total Vertical Depth: 1013 feet

Operator License No.: 35341
Op Name: RIVER ROCK OPERATING, LLC
Address: 211 N. ROBINSON SUITE 200
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1013		128 SX
SURF	8.625	20		4 SX

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 06/22/2018 11:30 AM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Revd. from: JORDAN JAMISON Company: RIVER ROCK OPERATING Phone: (620) 432-4200

Proposed Plugging Method: Circulate cement through tubing from TD to surface plus 10%. Top off cement at surface as needed. Cut off production casing 5ft below ground level. Reclaim location to original topography.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE
Date/Time Plugging Completed: 06/22/2018 11:30 AM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A cement string was lowered to TD and the well pumped full of cement from btm to top thru the cement string. The cement string was pulled to 200 ft and the well again pumped full. The cement string was removed and the well topped off with cement. According to operator, a total of 98 sacks of portland cement were used to plug well. The wellhead was cut off below plow depth and the location restored.

Perfs:

Top	Bot	Thru	Comments
960	963		
903	904		
897	899		

RECEIVED
KCC DIST # 3
JUL 13 2018
CHANUTE, KS

AD

INVOICED

JUL 20 2018

Remarks:

Plugged through: CSG

District: 03

Signed Alan Dunning
(TECHNICIAN)