

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-205-26553-00-00  
Spot: NWSESENW Sec/Twnshp/Rge: 24-29S-15E  
1983 feet from N Section Line, 1997 feet from W Section Line  
Lease Name: SHORT, STERLING Well #: 24-4  
County: WILSON Total Vertical Depth: 1227 feet

Operator License No.: 35341  
Op Name: RIVER ROCK OPERATING, LLC  
Address: 211 N. ROBINSON SUITE 200  
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1220		122 SX
SURF	8.625	44		20 SX
T1	2.375	1132		

Well Type: CM UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/21/2018 2:30 PM  
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC  
Proposal Rcvd. from: JORDAN JAMISON Company: RIVER ROCK OPERATING Phone: (620) 432-4200

Proposed Plugging Method: Circulate cement through tubing from TD to surface plus 10%. Top off cement at surface as needed. Cut off production casing 5ft below ground level. Reclaim location to original topography.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE  
Date/Time Plugging Completed: 06/21/2018 2:30 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A cement string was lowered to TD and the well pumped full of cement from btm to top. The cement string was pulled to 200 ft and the well again pumped full. The cement string was removed and the well topped off with cement. According to operator, a total of 105 sacks of portland cement were used to plug well. The wellhead was cut off below plow depth and the location restored.

Perfs:

Top	Bot	Thru	Comments
1125	1127		
1074	1076		
911	912		
897	899		
882	884		
840	843		
821	823		
762	766		
746	750		

RECEIVED  
KCC DIST # 3  
JUL 13 2018  
CHANUTE, KS

AD

INVOICED

JUL 20 2018

Remarks:

Plugged through: CSG

District: 03

Signed

Alan Dunning  
(TECHNICIAN)